
CLEARING & GRUBBING

PART 1 GENERAL**1.1 Related Work**

- .1 All Division 1 Specification Sections
- .2 Section [01561](#) Environmental Protection
- .3 Section [01740](#) Cleaning
- .4 Section [02050](#) Site Work Demolition & Removals
- .5 Section [02232](#) Tree Pruning

1.2 Measurement Of Payment

- .1 Measurement for payment will be as per the Bid Documents.

PART 2 PRODUCTS (NOT APPLICABLE)**PART 3 EXECUTION****3.1 Clearing**

- .1 Clear trees, shrubs, vegetation, uprooted stumps and surface debris not designated to remain and obstructions interfering with the Work on the approved plans or as stated on-site by the Consultant.
- .2 Cut off trees, brush, and scrub as indicated or as directed by Consultant at a height of not more than 300 mm above ground. In areas to be subsequently grubbed, height of stumps left from clearing operations to be not more than 1000 mm above existing ground.
- .3 Any required pruning to be conducted as per **Section [02232](#) Tree Pruning**.

3.2 Close Cut Clearing

- .1 Cut off trees, shrubs, stumps and other vegetation at ground level.
- .2 Perform close cut clearing by hand so that existing insulation of fibrous material is not damaged.
- .3 Cut off unsound branches and cut down trees over-hanging area cleared at no extra cost.

3.3 Isolated Trees

- .1 Cut off isolated trees as indicated or as directed by Consultant at height of not more than 100 mm above existing ground.

CLEARING & GRUBBING

3.4 Underbrush Clearing

- .1 Clear underbrush from areas as indicated at ground level.

3.5 Grubbing

- .1 Grub out stumps and roots to not less than 300 mm below existing ground surface.
- .2 Grub out visible rock fragments and boulders, greater than 300 mm in greatest dimension.

3.6 Protection

- .1 Prevent damage to existing fencing, trees landscaping, natural features, bench marks, existing buildings, existing pavement, utility lines, site appurtenances, water courses and root systems of trees which are to remain. Make good any damage to the satisfaction of the City of Brampton and the Consultant.

3.7 Remove And Disposal

- .1 Remove cleared and grubbed materials off site as indicated or designated by the Consultant.

3.8 Finished Surface

- .1 Leave ground surface in condition suitable for immediate operations.

END OF SECTION - 02231