



FIELD ORIENTATION

SETBACK FOR PROPERTY LINES AND OTHER FACILITIES.

PLANTING SETBACK AND PAYOUT LINES.

D1 - D8 FLOODLIGHTS ON DIRECT BURIED CONCRETE POLES TYPICAL. ELECTRICAL CABLES BURIED 800 MIN.

**NOTES:**

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE
2. SETBACK FROM LIGHT POLES TO SWALES, CATCH BASINS AND PLANTING TO BE MIN. 6000
3. MAX. 5% GRADE WITHIN 6000 R OF LIGHT POLES, FOR VEHICULAR ACCESS
4. D1 - D8 FLOODLIGHTS ARE SHOWN FOR GENERAL INFORMATION ONLY. REFER TO DRAWINGS AND SPECIFICATIONS BY THE ELECTRICAL ENGINEER



**PLANNING,  
DESIGN &  
DEVELOPMENT  
DEPARTMENT**

**TITLE: SENIOR SOCCER  
(FIELD AND LIGHTING LAYOUT)**

**DRAWING NO.  
PDD 450**

REVIEWED BY: *SP*

SCALE: **N.T.S.**

APPROVED BY: *Steve Walsh*

DATE: **JANUARY 2007**