



CONCRETE BLOCK

NOTES:

1. PROVIDE CONCRETE BLOCKS 3048 ON CENTRE AND AT THE END OF PARKING ROWS.
2. STEEL PIPE RAIL SHALL BE SCHEDULE 40 - 50 DIA. x 3.2 WALL, HOT-DIPPED GALVANIZED, SUPPLIED IN 3048 LENGTHS.
3. ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.



**PLANNING,
DESIGN &
DEVELOPMENT
DEPARTMENT**

**TITLE:
PRECAST CONCRETE
BLOCK AND RAIL PARKING GUIDES**

**DRAWING NO.
PDD 520**

REVIEWED BY: *SH [Signature]*

SCALE: **N.T.S.**

APPROVED BY: *[Signature]*

DATE: **JANUARY 2007**