



**NOTES:**

EXCAVATION: 275 MINIMUM DEPTH, OR AS REQUIRED. CONTRACTOR SHALL CONTACT THE CITY IMMEDIATELY IF UNSUITABLE OR UNSTABLE SUBGRADE IS ENCOUNTERED, SUCH AS EXCESSIVE TOPSOIL, SOFT SPOTS, AND/OR ORGANIC MATTER. METHODS AND/OR MATERIAL MUST BE APPROVED BY THE CITY PRIOR TO COMMENCING WORK. SUBGRADE TO BE CONSOLIDATED AND TESTED TO 98% S.P.D. MIN. REMOVE EXCESS MATERIAL OFF SITE UNLESS OTHERWISE DIRECTED BY THE CITY.

GRANULAR BASE: 200 MIN. LAYER OF 19 CRUSHER RUN COMPACTED TO 98% STANDARD PROCTOR DENSITY MIN.

ASPHALT: 75 MM COMPACTED DEPTH OF HOT MIX HL.3 ASPHALTIC CONCRETE.

EDGE TREATMENT: ASPHALT EDGE TO BE 45 DEGREES, TAMPED TO FORM UNIFORMLY, SMOOTH, CLEAN EDGES, WITHOUT LATERAL DEVIATIONS. SOD TO MEET AND MATCH EXISTING GRADES, WITH SMOOTH TRANSITIONS AT A MAXIMUM SLOPE OF 4:1. ALL SEEDED AND/OR SODDED AREAS SHALL BE 25 BELOW THE FINISH ELEVATION OF ASPHALT. REMOVE EXCESS TOPSOIL AND SOD AS DIRECTED.

DRAINAGE: GRADE WALKWAY WITH A 2% CROSS-SLOPE OR AS DIRECTED ON SITE. **PONDING WATER ON ASPHALT WALKWAYS WILL NOT BE ACCEPTED.**

SODDING: ALL DISTURBED AREAS SHALL BE SODDED (AND/OR SEEDED) OVER 150 TOPSOIL (LIGHTLY COMPACTED), MINIMUM WIDTH OF 900 mm. REFER TO PLAN.

ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.