
SITE FURNITURE

PART 1 GENERAL**1.1 Related Work**

- .1 All Division 1 Specification Sections
- .2 Section [02785](#) Unit Pavers
- .3 Section [02868](#) T-Ball Backstops
- .4 Section [03100](#) Concrete Formwork
- .5 Section [03200](#) Concrete Reinforcement
- .6 Section [03300](#) Cast-In-Place Concrete

1.2 Source Quality Control

- .1 Supply manufacturer's samples of finishes and anchoring systems and Shop Drawings for approval by the Consultant.
- .2 **All furniture to be a City of Brampton approved standard unless otherwise noted in this section.** Refer to the Planning and Infrastructure Services Department website link indicated below for all Streetscape & Parks Construction Standard Details:

<http://www.brampton.ca/en/Business/planning-development/guidelines-manuals/Pages/Streetscape-Parks-Construction-Standard-Detail.aspx>

- .3 Refer to **Section 01095 Referenced Guidelines** for a list of all Streetscape & Parks Construction Standard Details.

1.3 Inspection

- .1 Refer to Section [01450](#) **Quality Control & Inspection**

1.4 Shop Drawings and Product Literature

- .1 Submit Shop Drawings and product data as requested by the Consultant.
- .2 Indicate dimensions, sizes, assembly, anchorage and installation details for each furnishing specified

1.5 Maintenance Data

- .1 Provide maintenance data for care and cleaning of site furnishings at the time of project close out as specified in Section [01700](#) **Contract Closeout, Takeover & Warranties.**

SITE FURNITURE

PART 2 PRODUCTS**2.1 Site Furniture**

- .1 Refer to drawings for the required site furniture.

PART 3 – EXECUTION**3.1 Installation**

- .1 Install site furniture square and plumb as shown on the Contract Document drawings.
- .2 Assemble furnishings in accordance with manufacturer's instructions.
- .3 Touch up damaged finished to the satisfaction of the Consultant.
- .4 Anchoring: All site furniture is to be surface mounted to concrete (as per manufacturer's specifications) or through unit paving into a concrete base (Contractor to use 300mm long threaded connecting rods). Anchoring system is to be drilled and secured with expansion epoxy grout as supplied by approved manufacturer.
- .5 Use tamper-proof nuts.

END OF SECTION - 12500