



THE CORPORATION OF THE CITY OF BRAMPTON

BY-LAW

Number 129 - 2022

To amend Comprehensive Zoning By-law 270-2004, as amended

The Council of the Corporation of the City of Brampton, in accordance with the provisions of the *Planning Act, R.S.O. 1990, c.P. 13*, hereby ENACTS as follows:

1. By-law 270-2004, as amended, is hereby further amended:

(1) by changing on Schedule A thereto of the By-law the zoning designation of the lands shown outlined on Schedule A attached to this by-law

From:	To:
"Residential Extended One Zone (R2B(1))"	"Residential Townhouse C – Section 3022 (R3C-3022)"

2. by adding thereto the following section:

"3022 The lands designated R3C-3022 on Schedule A to this by-law:

3022.1 shall only be used for the purpose of a townhouse dwelling.

3022.2 shall be subject to the following requirements and restrictions:


- 1) For the purposes of this section the lot line abutting Haggert Avenue shall be the front lot line.
- 2) All lands zoned R3C-3022 shall be treated as one lot for zoning purposes.
- 3) Minimum Lot Area: 60 square metres per dwelling unit.
- 4) Minimum Yard Setback for a Principle building:
 - a. 2 metres to the lot line abutting Haggert Avenue;
 - b. 7 metres to the rear lot line if residential parking is provided at 70 degrees up to and including 90 degrees;
 - c. 6.75 metres to the rear lot line if residential parking is provided at 50 degrees up to 70 degrees;
 - d. 3.7 metres to the lot line abutting Jessie Street;
 - e. 11 metres to the interior side lot line;
 - f. 0.0 metres to a private road or common element.

- 5) Minimum Dwelling Unit Width: 5.5 metres;
- 6) Maximum Number of Dwelling Units: 6 units;
- 7) Maximum Building Height: 10.6 metres;
- 8) Minimum Aisle Width serving residential parking spaces - 70 degrees up to and including 90 degrees: 6 metres;
- 9) Minimum Aisle Width serving residential parking spaces - 50 degrees up to 70 degrees: 5.75 metres
- 10) Minimum Aisle Width serving visitor parking spaces: 5.5 metres;
- 11) Minimum Landscaped Open Space: No requirement;
- 12) Common Amenity Area: No requirement;
- 13) Garage Control: No requirement."


ENACTED and PASSED this 1st day of June, 2022.

Approved as to
form.
2022/05/27
SDSR


Approved as to
content.
2022/05/27
AAP




Martin Medeiros, Deputy Mayor



Peter Fay, City Clerk






SUBJECT LANDS

RAILWAYS



KEY MAP