



BUILDER BULLETIN #2016-04

(December 15, 2016)

IMPORTANT NOTICE TO BUILDERS

HOLIDAY HOURS

The City of Brampton offices will be closed from noon on Friday, December 23, 2016 to Monday, January 2, 2017, inclusive. Regular business hours resume on Tuesday, January 3, 2017.

COLD WEATHER CONSTRUCTION

The regulations of the Ontario Building Code governing cold weather construction are attached. Please ensure this information is forwarded to your site offices and complied.

IMPORTANT NOTICE

COLD WEATHER CONSTRUCTION REQUIREMENTS

In accordance with the Ontario Building Code, the following must be adhered to during cold weather construction:

- Div. B Article 7.3.5.4. Where piping may be exposed to freezing conditions, it shall be protected from the effects of freezing.
- Div. B Article 9.3.1.9. (1) When the air temperature is below 5°C (41°F), concrete shall be,
 (a) kept at a temperature of not less than 10°C (50°F) or more than 25°C (77°F) while being mixed and placed, and
 (b) maintained at a temperature of not less than 10°C (50°F) for 72 hours after placing.
(2) No frozen material or ice shall be used in concrete described in Sentence (1).
- Div. B Article 9.8.10.3. Suitable precautions shall be taken during backfilling and grading operations to ensure that subsequent freezing of the soil will not cause uplift forces on the underside of cantilevered concrete steps or the walls to which they are attached will be damaged.
- Div. B Article 9.10.20.5. Equipment forming part of a fire protection system that may be adversely affected by freezing temperatures and that is located in an unheated area shall be protected from freezing.
- Div. B Article 9.12.1.3. The bottom of excavations shall be kept from freezing throughout the entire construction period.
- Div. B Article 9.20.14.1. (1) Mortar and masonry shall be maintained at a temperature not below 5°C (41°F) during installation and not for less than 48 hours after installation.

 (2) No frozen material shall be used in the mortar mix.
- Div. B Article 9.20.14.2. The top surface of uncompleted masonry exposed to the weather shall be completely covered with a waterproofing material when construction is not in progress.
- Div. B Article 9.28.6.1. (1) The base for stucco shall be maintained above freezing.

 (2) Stucco shall be maintained at a temperature of not less than 10°C (50°F) during application and for not less than 48 hours afterwards.
- Div. B Article 9.29.5.10. In cold weather, heat shall be provided to maintain a temperature of not below 10°C (50°F) for 48 hours prior to taping and finishing and maintained for not less than 48 hours after that.