

# City of Brampton LRT Extension Study Council Workshop 2



# 01 Introduction

## **Timeline and Council Decisions**

**Sept 2014** 

Transit Project Assessment Process (TPAP) for Hurontario-Main LRT was approved.

**April 2015** 

Province announced funding for the Hurontario-Main LRT.

Oct 2015

Brampton Council approved construction of the LRT to Steeles Ave only.

Feb 2017

Brampton Council directed staff to study alternate LRT routes from Steeles Avenue into Downtown Brampton.

**Dec 2018** 

Brampton Council directed staff to prioritize the LRT route along Main Street as originally recommended in the 2014 TPAP.

## **Timeline and Council Decisions**

**May 2019** 

Brampton Council approved the study that would update the 2014 approved TPAP alignment and bring the LRT up Main Street.

**June 2020** 

Update to Council on the long list and short list of LRT alignments into Downtown Brampton that were being considered.

**March 2021** 

Update to Council on the short list of LRT alignments and the Metrolinx Preliminary Design Business Case for each of these alignments.

**June 2021** 

Council directed staff to take both the preferred surface and preferred tunnel alignments through the 30% Design and Draft Environmental Project Report phase.

Feb 2023

Today's Council Workshop

## **Study Process**

- The study evaluated LRT options in a multi-level process.
- Over the course of the study, the options were evaluated, presented to the public and narrowed down to one surface and one underground for preliminary design.
- Only one option will be taken through the Transit Project Assessment Process (TPAP).



# **Investment Options**

- The long list of investment options was evaluated and presented to stakeholders and the public and narrowed down to a short list.
- Short listed options were further evaluated in a Preliminary Design Business
  Case (PDBC). Findings of the PDBC were presented to City Council in March
  2021 which confirmed the preferred options for preliminary design.

Long List	Short List	Preferred
<ul><li>6 Surface Options</li><li>2 Underground Options</li></ul>	<ul><li>4 Surface Options</li><li>2 Underground Options</li></ul>	<ul><li>1 Surface Option</li><li>1 Underground Option</li></ul>
2 Loop Options		

## **Public Feedback**



**54%** UNDERGROUND

46% SURFACE



Public preference for the preferred options according to the 131 community members who responded to the survey.




# **Key Themes Identified at Virtual Open House #2**

- Revitalize Downtown
- Shorten travel time to Downtown
- Create a transit hub at Brampton GO with easy transfers
- Protect for a northern extension
- Increase opportunities for cycling

# 02 Preferred Surface Option

# **Preferred Surface Option**



# **Surface Option: Key Design Considerations**

1 TRANSPORTATION IMPACTS

Higher travel times, access modifications, and cycling network gap

OPERATION &
MAINTENANCE RISKS

Risks related to streetlighting, overhead catenary system, and road maintenance

2 IMPACTS TO DOWNTOWN

Lowering of Main St under CN Bridge and impact to Downtown Revitalization cross-section

5 PROPERTY IMPACTS

Impacts to heritage features from TPSS and Brampton GO Station property taking

FUTURE EXTENSION

Considerations for future northern extension

6 BRAMPTON GO STATION

Updates to the design at the Brampton GO LRT terminus station




## TRANSPORTATION IMPACTS

**Higher Travel Times and Access Modifications** 

Mode	Direction	Surface Option Travel Time (min)	Underground Option Travel Time (min)
Transit	NB	10 min	7 min
Hansii	SB	9 min	7 min
Auto	NB	24 min	7 min
Auto	SB	7 min	7 min

- All left turn phases parallel to the LRT corridor operate under a "protected-only" phase to avoid any potential vehicle conflicts.
- U-turns are only allowed at signalized intersections.
- Most residential and business access will be accessible on a right-inright-out (RIRO) basis. Drivers wishing to turn left will require a U-turn at the nearest signalized intersection with a protected left turn phase.

New signalized intersections at: Peel Village, Pine Ridge, Harold, Clarence, and Nelson




Note: All values reported are for the PM peak hour



#### Cycling Network Gap


- Cycling in Segment B was considered but is not feasible without widening the right-of-way:
  - Widening to accommodate cycling was not advanced because of additional 6,180 m<sup>2</sup> of property needed, removal of 148 trees and injury to 111 trees
  - The project team reviewed additional options. LRT in mixed traffic in curb lanes was investigated but not advanced due to significant impacts on transit time (+50%) and ridership (-10%).
- To mitigate the gap, three parallel cycling connections with connections to Main St have been identified:
  - Mill Street South: on-street, one-way cycling facility (new)
  - Elizabeth Street South: on-street, one-way cycling facility (new)
  - Existing Etobicoke Creek Recreational Trail
- An additional bridge crossing Etobicoke Creek is recommended through Steacy Park to connect the trail network to Main Street.







- To accommodate LRT overhead catenary system (OCS), Main St must be lowered by ~1 m under CN bridge.
- Results in impacts between Queen and Church St, including ramps and railings at intersections and a constrained pedestrian environment.
- Requires regrading of side streets (on Nelson St E/W and Theater Ln).










- To accommodate LRT overhead catenary system (OCS), Main St must be lowered by ~1 m under CN bridge.
- Results in impacts between Queen and Church St, including ramps and railings at intersections and a constrained pedestrian environment.
- Requires regrading of side streets (on Nelson St E/W and Theater Ln).










### IMPACTS TO DOWNTOWN

Changes to Downtown Revitalization Cross-section


As a result of the lowering of Main St and the introduction of LRT at the surface in Downtown, changes to the Downtown Revitalization cross-section elements are required:

- Pedestrian clearway reduced
  - 3 m to 1.5 m at station platforms
- Furnishing/planting zone eliminated/reduced
  - Eliminated where station platform exists
  - Reduced from 1.2 to 1 m elsewhere
- · Buffer to cycling facility reduced
  - Sub-optimal buffer to travel lane (and LRT)
  - Adjacent to sidewalk (higher potential for conflicts)

#### **Downtown Revitalization Cross-Section (2022)**




#### **LRT Extension Cross-Section (2022)**



# 3 FUTURE EXTENSION

 Options to extend the LRT north in the future are limited due to track geometry and the LRT being underground at its terminus



# OPERATION & MAINTENANCE RISKS

Operating LRT in a constrained corridor presents several O&M risks:

- Potential LRT service disruptions due to:
  - mode conflicts (vehicular traffic especially in mixed traffic conditions)
  - maintenance activities (utilities, streetlighting, etc)
  - emergency services (fire, EMS)
- Difficulty in accommodating adequate clearances between overhead catenary system (OCS) conductors and street light infrastructure for maintenance. Would require change to approach for maintenance agreements between Brampton and LRT operator.





# 5 MAJOR PROPERTY IMPACTS

Location	Description	Mitigation
Guest St	<ul> <li>Potential impact on listed heritage property due to location of TPSS near Guest Street.</li> </ul>	<ul> <li>Mitigation measures range from in-situ retention of the building, adaptive re- use, relocation within and outside of the</li> </ul>
Brampton GO Station Area	<ul> <li>Permanent property taking for LRT track and TPSS.</li> <li>Temporary property taking at Brampton GO for construction of LRT station and tail track.</li> </ul>	property or demolition and salvage.  Coordination with affected property owner.

**Note:** Consultation with affected property owners to occur once a preferred option is selected.








- Through design development it was determined that the Brampton GO LRT terminus station would have to be built underground (cut and cover) due to:
  - updated track geometry pushing the station further west
  - provision for connections to Brampton GO Station
  - maintaining the GO Station surface parking lot
- Integrating the LRT and GO stations was not contemplated in previous designs.
- Assumptions made in the 2014 Hurontario-Main LRT TPAP do not reflect the constraints of the currently under construction Hurontario LRT.






# 03

# **Preferred Underground Option**

# **Preferred Underground Option**



# **Underground Option: Key Design Considerations**

- 1 TUNNELING APPROACH
  Construction methodology
- 2 UNDERGROUND STATIONS
  Property requirements and design updates at Nanwood Station and Downtown Brampton
- PORTAL RELOCATION
  Increased tunnel length and portal size due to portal relocation out of floodplain



- Cut and cover construction proposed between tunnel portal (south of Elgin Drive) to Nanwood Drive
- Nanwood Station to be constructed via open cut construction partially within the existing street right-of-way
- Sequential Excavation Mining (SEM tunnelling) north of Nanwood Station to the Brampton GO Station terminating at Church St
- Opportunity for a second mining operation has been protected for at the Brampton GO Station to fast-track work, to be determined if required in future phases of work






#### **Nanwood Station**

 Increase in size of station footprint due to design development

#### **Downtown Brampton Station**

 Increase in size of station due to design development and inclusion of secondary station entrance/exit (with stairs and escalators) to serve Queen/Main intersection





Location	Description	Mitigation
Nanwood Station	<ul> <li>Permanent and temporary takings required for station entrance building, emergency exit building, active transportation improvements and for construction staging area (tunneling activities)</li> </ul>	<ul> <li>Coordination with affected property owners as a result of temporary and permanent impacts.</li> </ul>
Downtown Brampton / Brampton GO Station	<ul> <li>Permanent property taking required for station buildings and potential additional construction staging area related to tunneling activities.</li> </ul>	

**Note:** Consultation with affected property owners to occur once a preferred option is selected.



Downtown Brampton / Brampton GO Station



### **PORTAL RELOCATION**

Increased tunnel length due to portal relocation out of floodplain

- The TRCA requested the portal be relocated south outside of the Etobicoke Creek floodplain to minimize risk to loss of property / life.
- This resulted in a 270 m longer underground tunnel which increased the underground option capital cost.
- Additional mitigation measures to protect the portal from intrusion will be investigated in future phases of work.



# O4 Cost Update

# **Surface Option — Cost Drivers**



1. Increase in length of trackworks to accommodate tail tracks (vehicle storage allows for enhanced flexibility in operations).



2. Inclusion of Brampton Gateway Station Relocation Costs (previously not included in 2021 cost estimate).



3. Design updates at Brampton GO LRT terminus (underground station, including connections to GO\*).



4. Lowering of Main Street required under the CN bridge to accommodate overhead catenary system (OCS) for LRVs.



5. High Inflation for Major Construction Projects (e.g. Ontario Line costs going from \$10B in 2019 to \$19B in late 2022)

<sup>\*</sup> Note: Cost sharing with other stakeholders could be explored to reduce the financial impact to the project.

# **Cost Update – Surface Option**

	Item	Class 4/5 Estimate \$ 422 M	
	Previous Cost Estimate		
	Design Updates	+ \$ 310 M	
1	Tail tracks	\$ 42 M	
2	Gateway Terminal Station relocation cost	\$ 9 M	
3	Brampton GO LRT Terminus Station	\$ 216 M	
4	Lowering of Main Street between Church and Queen St	\$ 43 M	
	Inflation and New Cost Data Obtained	+ \$ 201 M	
	Current Cost Estimate	\$ 933 M	

## **Underground Option — Cost Drivers**















- Increase in length of trackworks to accommodate tail tracks (vehicle storage allows for enhanced flexibility in operations).
- Inclusion of Brampton Gateway Station relocation costs (previously not included in 2021 cost estimate).
- 3. Design updates at Brampton GO terminus (larger station footprint, additional entrance/exit).
- Design updates at Nanwood Station (larger station footprint). 4.
- Relocation of tunnel portal (increase in portal length, increase in tunneling length).
- Increase in cost related to earthworks, bridge works, streetscaping, utility works and 6. allowances as a result of more advanced design.
- High Inflation for Major Construction Projects (e.g. Ontario Line costs going from \$10B in 2019 to \$19B in late 2022)


# **Cost Update – Underground Option**

	Item	Class 4/5 Estimate	
	Previous Cost Estimate	\$ 1,700 M	
	Design Updates	+ \$ 460 M	
1	Tail tracks	\$ 92 M	
2	Gateway Terminal Station relocation	\$ 9 M	
3	Brampton GO Station	\$ 75 M	
4	Nanwood Station	\$ 46 M	
5	Portal Relocation	\$ 167 M	
6	Other Costs	\$ 71 M	
	Inflation and New Cost Data Obtained	+ \$ 644 M	
	Current Cost Estimate	\$ 2,804 M	

# 05 Summary Comparison


# **Segment A Comparison**


- The design is generally the same for the surface and underground options in Segment A.
- The underground option has the portal in Segment A and an underground station at Nanwood as compared to the surface option.



# Segment B Comparison

- Underground option results in faster travel times for autos/transit and fewer access restrictions.
- Surface option cannot accommodate cycling lanes on-street; where as, the underground option can.
- Surface option TPSS #2 impacts a "listed" heritage property.
- Underground option has no operating and maintenance risks compared to the surface option.






# Segment C Comparison

- Underground option results in faster travel times for autos/transit and fewer access restrictions.
- Surface option results in a condition that is not optimal and does not achieve the vision set out in Downtown Reimagined.
- Underground option has no operating and maintenance risks as compared to the surface option.
- Surface option is more complex to extend in the future compared to underground.









# **Summary Comparison**

Worse Comparable Better

Key Differentiators		Surface Option	Underground Option
	Transit Travel Time	Higher (~ 9 – 10 min)	Lower (~ 7 min)
	Auto Travel Time	Higher (~ 7 – 24 min)	Lower (~ 7 min)
Transportation	Daily Ridership	Lower (29,500)	Higher (30,400)
Impacts	Access Restrictions	RIRO restrictions and banned left turns	RIRO restrictions in Segment A only
	Bridge Modifications	Required for Etobicoke Creek North and South Bridge	Required only for Etobicoke Creek South Bridge
	Cycling Infrastructure	No cycling in Segment B	Continuous cycling facilities on Main St
Impacts to	Lowering of Main Street	Results in constrained cross-section, ramps/railings	No lowering, no impacts
Downtown	Downtown Revitalization	Does not achieve Downtown Revitalization vision	Accommodates Downtown Revitalization design
Future Extension	Ease of Extension	Challenges in extending the LRT line in the future	No challenges in extending the LRT line in the future
Operations & Maintenance	O&M Risks	Risks to LRT service (disruption), roadway maintenance activities (illumination), emergency services (fire, EMS).	LRT underground, minimal risks
Property	Heritage Impacts	TPSS2 impacts "listed" heritage property	Minimal impact to built and cultural heritage
Impacts	Permanent and Temporary Takings	Fewer Permanent Property Takings Higher Temporary Property Takings	Higher Permanent Property Takings Fewer Temporary Property Takings
Other	Cost	Lower (\$933 M)	Higher (\$2.8 B)
	Schedule	Shorter total implementation schedule (6 years)	Longer total implementation schedule (7 to 8 years)

# **Summary Comparison**

- While the surface option is one-third the cost of the underground option, it has significant disbenefits in terms of travel time, ability to achieve the vision for Downtown Brampton, operations/maintenance risks, and heritage impacts.
- Although the underground option is more costly, it provides real travel time savings for transit riders, pedestrians, cyclists, and motorists and allows the City to achieve its vision for Main St and Downtown Brampton while limiting risks for implementation and operation.



# **Next Steps**

- Receive feedback from key stakeholders.
- A single option would be selected to take through the final Transit Project Assessment Process (TPAP).

